



NOTES:

VALVES INSIDE METER BOX TO BE OPEN LEFT BALL VALVES AS PER SPECIFICATIONS. ALL VALVES TO BE "T" HEAD.

VAULT TO BE CONSTRUCTED FROM PRECAST REINFORCED RIBBED CONCRETE WALL PANELS.

METER CONFIGURATION MAY VARY DUE TO BRAND SUPPLIED.

BOTTOM SLAB TO BE SAME AS WALL PANELS WITH FLAT SIDE UP.

ALL JOINTS ARE TO BE PACK JOINT CONNECTIONS.

USE 18" GALVANIZED NIPPLES FOR SUPPORT.

MUST BE FORD ONLY.

TAPS TO MAIN MUST INCLUDE SERVICE SADDLES.

**CHARLOTTE-MECKLENBURG
UTILITY DEPARTMENT
ENGINEERING DIVISION
CHARLOTTE, NORTH CAROLINA**

Job No. _____ File No. _____		STANDARD DETAIL WATER					
Scales PLAN NO SCALE							
PROFILE Hor. _____ Vert. _____		1 1/2" & 2" SETTER 2' x 3' x 31" VAULT					
As Built _____ Date _____							
Surveyed By	Designed By	Drawn By	Project-Engr	Approved By	Date	Sheet	Of
		JFB		R.D. Mandy	2/01	27	

No.	Date	By	Revision

S0427.DWG
11/29/99