



# Charlotte Department of Transportation

## Memorandum

---

**Date:** September 25, 2008

**To:** Tom Drake & Tammie Keplinger  
Charlotte-Mecklenburg Planning Department

**From:**   
Scott L. Putnam  
Development Services Division

**Subject:** Rezoning Petition 08-141: Located on the southwest corner of South Tryon Street and West Tremont Avenue

---

**Consistency with Transportation Action Plan (TAP):** The two goals of the TAP that most directly affected the staff's review of this petition define the integration of land use and transportation, and the provision of transportation choices.

- Goal 1 of the TAP relies on the Centers, Corridors and Wedges land use strategy to be implemented. This project site is located in a Corridor and appears to support the Centers, Corridors and Wedges land use strategy.
- Goal 2 of the TAP describes various connectivity and design features that are important for motorists, pedestrians and bicyclists. Specific comments are identified below that need to be addressed for CDOT's support of the petition and to bring the site plan into compliance with the TAP and best practices for multimodal transportation.

### Vehicle Trip Generation

With the array of uses allowed in I-2 and TOD zoning categories, a wide range of trip generation is possible for either the existing or proposed zoning scenarios. Given the size of the site, its proximity to the good street network in the area, CDOT feels that there should only be minor impacts to the transportation system resulting from this rezoning.

We have the following specific comments that are critical to CDOT's support of the rezoning petition:

1. The South End Transit Station Area Plan includes a new cross-section for South Tryon Street with a 60' back-of-curb width, whereas the current cross-section varies between 41 and 47 feet. Therefore, the TOD setback will be measured from the back of the future curb line, 30 feet from the existing centerline.

We have the following general comments that are provided to aid the petitioner in planning and subsequent permitting phases:

Adequate sight triangles must be reserved at the existing/proposed street entrance(s). Two 35' x 35' and two 10' x 70' sight triangles are required for the entrance(s) to meet requirements. All

Tom Drake & Tammie Keplinger

September 25, 2008

Page 2 of 2

proposed trees, berms, walls, fences, and/or identification signs must not interfere with sight distance at the entrance(s). Such items should be identified on the site plan.

The proposed driveway connection(s) to S. Tryon Street will require a driveway permit(s) to be submitted to CDOT and the North Carolina Department of Transportation for review and approval. The exact driveway location(s) and type/width of the driveway(s) will be determined by CDOT during the driveway permit process. The locations of the driveway(s) shown on the site plan are subject to change in order to align with driveway(s) on the opposite side of the street and comply with City Driveway Regulations and the City Tree Ordinance.

Any fence or wall constructed along or adjacent to any sidewalk or street right-of-way requires a certificate issued by CDOT.

A Right-of-Way Encroachment Agreement is required for the installation of any non-standard item(s) (irrigation systems, decorative concrete pavement, brick pavers, etc.) within a proposed/existing City maintained street right-of-way by a private individual, group, business, or homeowner's/business association. An encroachment agreement must be approved by CDOT prior to the construction/installation of the non-standard item(s). Contact CDOT for additional information concerning cost, submittal, and liability insurance coverage requirements.

If we can be of further assistance, please advise.

SLP

c: R. H. Grochoske (via email)  
J. A. Carroll – Review Engineer (via email)  
B. D. Horton (via email)  
A. Christenbury (via email)  
M. A. Makoid (via email)  
Doug Stephan (via email)  
NCDOT/Louis Mitchell (via email)  
NCDOT/Scott Cole (via email)  
Rezoning File