



PLAN REVIEW SHEET

Date: 8/29/2024

Petition #: 2024-080

Staff Contact: Evan Punch

The Site is located along Oneida Rd and is served by CATS bus route #22. CATS requires the existing bus stop to be upgraded to an ADA-compliant bus detail 60.01A. The final location will be coordinated with the developer during the Land Development plan review process.

LEGEND

- BOARDING AND ALIGHTING AREA: [---]
- BUS SIGN: |
- CONCRETE 4" THICK: [---]
- TRASH RECEPTACLE: ○

NOTES

- DIMENSIONS REPRESENT MINIMUM STANDARDS, VARIATIONS MUST BE APPROVED THROUGH CATS AND CDOT PROJECT MANAGER.
- WIDTH OF EXISTING SIDEWALK PLUS PLANTING STRIP WIDTH MUST EQUAL 8' WIDE. IF WIDTH IS LESS THAN 8', EXISTING SIDEWALK MUST BE REPLACED WITH WIDER SIDEWALK TO OBTAIN 8' WIDTH.
- SEE SHEET NO. 60.07A, 60.07B, AND 60.07C FOR ADDITIONAL DETAILS AND NOTES.

PLAN VIEW

5' WIDE SIDEWALK 4" THICK

SIDEWALK MUST MATCH SLOPE OF BOARDING AND ALIGHTING AREA

R/W

R/W

R/W

RIGHT OF WAY

R=2'

PLANTING STRIP 2' MIN. WIDTH, VARIES

CURB

GUTTER

STREET

3'-

2'-

5'-

NO. DATE DESCRIPTION

APPROVED DATE _____

CATS
CHARLOTTE AREA TRANSIT SYSTEM

BUS STOP WITH PLANTING STRIP, MINIMUM WIDTH

STD. NO.	REV.
60.01A	