

Rezoning Transportation Analysis

Petition Number: 2024-038

General Location Identifier: 04322129

From: Jake Carpenter, PE

Jacob.carpenter@charlottenc.gov

980-221-5675

Reviewer:

Isaiah Washington

Isaiah.Washington@charlottenc.gov

980-221-5778

Revision Log:

Date	Description
04-24-24	First Review (JT)
05-06-24	Trip Generation Update
06-03-24	Trip Generation Update

General Review Information

The petition is located at the intersection of WT Harris Boulevard, a State-maintained expressway, and Davis Lake Parkway, a City-maintained major collector. The petition is located in a northeast wedge outside of Route 4.

Active Projects Near the Site:

- TIP - W W.T. Harris Boulevard (NC 24)
 - TIP Number: Not applicable
 - Advanced Project Description: Widen from 4 lanes to 6 lanes, with median and multi-use path
 - ROW Year: Undetermined
 - Construction Year: Undetermined

CDOT's review of this rezoning petition is intended to provide consistency with council adopted policies, plans, standards and guidelines including, but not limited to, the [Transportation Action Plan \(TAP\)](#), [Vision Zero](#), [Urban Street Design Guidelines \(USDG\)](#), [Center, Corridor and Wedges](#), [Charlotte BIKES](#), [Traffic Impact Study Guidelines](#) and [Charlotte WALKS](#). With a commitment to design complete streets, this review is to ensure that the City's transportation network supports current and future land uses and includes streets that provide safe and comfortable mobility for motorists, pedestrians, bicyclists, and transit users.

This document is primarily for communication to Planning Department staff as part of the overall City staff analysis of the rezoning petition and includes an overall summary of the case from a transportation perspective, information on trip generation, and resolved or outstanding site plan concerns. Additional advisory information about the driveway permit process is provided for information only.

Based on our review of the petition, we offer the following information for your consideration.

Transportation Summary

The site is located at the intersection of WT Harris Boulevard, a State-maintained expressway, and Davis Lake Parkway, a City-maintained major collector. A Comprehensive Transportation Review (CTR) is not necessary for the complete review of this petition due to the conventional rezoning. A CTR will be required during permitting if the site generates site trips over ordinance thresholds. The site will be subject to transportation improvements in accordance with the UDO and the adopted CDOT Streets Map. CDOT will work with the petitioner during the permitting process to pursue all options to provide additional forms of connectivity that reflect the types of development associated with this place type and zoning district.

Rezoning Transportation Analysis

Petition Number: 2024-038

General Location Identifier: 04322129

Trip Generation

Scenario	Land Use	Intensity	Trip Generation (vehicle trips/day)	Source
Existing Use	Warehousing	18,844	110	<i>Tax Record</i>
Existing Use	Vacant	-	-	<i>Tax Record</i>
Entitlement with Current Zoning	CG (3.02 acres)	-	-	<i>General Guidance from Planning</i>
Entitlement with Current Zoning	Retail (CC, 3.02 acres)	15,000 SF	863	<i>General Guidance from Planning & RZP# 2013-024</i>
Proposed Zoning	Retail (CG 3.02 acres)	45,300 SF	2,145	<i>General Guidance from Planning</i>

Petitioner to provide responses to the staff comments below as well as specify other changes to the site plan.

Outstanding Issues

Strikethrough = Resolved

1. Comprehensive Transportation Review (CTR):

A Comprehensive Transportation Review (CTR) is not necessary for the complete review of this petition. If during the permitting process the site generates the designated number of trips outlined on Table 3.1 in the Charlotte Streets Manual, then a Comprehensive Transportation Review will be required.

Advisory Information

The following are requirements of the developer that must be satisfied prior to driveway permit approval. These requirements shall be reflected on the rezoning plan, as appropriate.

1. CDOT has the authority to regulate/approve all private street/driveway and public street connections to the right-of-way of a street under the regulatory jurisdiction of the City of Charlotte, per the City of Charlotte's Driveway Regulations.
2. Adequate sight triangles must be reserved at the existing/proposed street entrance(s). Two 50' x 50' sight triangles (and two 10' x 70' sight triangles on NCDOT-maintained streets) are required for the entrance(s) to meet requirements. All proposed trees, berms, walls, fences, and/or identification signs shall not interfere with sight distance at the entrance(s) and shall be identified on the site plan.
3. The proposed driveway connection(s) to public streets will require a driveway permit(s) to be submitted to CDOT (and NCDOT on NCDOT-maintained streets) for review and approval. The exact driveway location(s) and type/width of the driveway(s) will be determined by CDOT during the driveway permit process. The locations of the driveway(s) shown on the site plan are subject to change in order to align with driveway(s) on the opposite side of the street and comply with City Driveway Regulations and the City Tree Ordinance.
4. All proposed commercial driveway connections to a future public street will require a driveway permit submitted to CDOT for review and approval.
5. Any fence or wall constructed along or adjacent to any sidewalk or street right-of-way requires a certificate issued by CDOT.
6. To obtain a street and pedestrian lighting recommendation, the petitioner should visit the following link: <https://charlottenc.gov/Transportation/Programs/Pages/StreetLighting.aspx>