



**MECKLENBURG COUNTY**  
**Land Use & Environmental Services Agency**

**MEMORANDUM**

To: Charlotte-Mecklenburg Planning Commission  
From: LUESA, Mecklenburg County  
Date: 6.27.24  
Subject: Rezoning Petition Comments

Charlotte-Mecklenburg Planning Commission  
600 East Fourth Street Charlotte, North Carolina 28202

Mecklenburg County has reviewed the City of Charlotte rezoning petition below to identify regulatory requirements of the petitioner; inform the petitioner, planning staff, and other affected parties of such regulatory requirements; and identify potential effects on, and impacts from, nearby properties.

<b><u>Petitioner Information:</u></b> Chandni Lalchandani 10215 Pinecroft Creek Ln Matthews, NC, 28105 Home Phone: 980-334-2003 lisa.arnold@alexanderricks.com	<b><u>Parcel GIS ID(s):</u></b> 18701102, 18701101
--	---

**2024-059: Veer Homes - Sardis Lane**

Air Quality Comments: Demolition or renovation of existing structures may require proper notification and removal of asbestos. A letter of notification and the required forms have been mailed directly to the petitioner.

Ground Water Services Comments: Executive Summary- Contamination incidents exist in the vicinity, so there may be restrictions for water supply wells. Water supply well registration records noted for parcel 187-011-02.

Groundwater & Wastewater Services records indicate contamination site(s) exist on or within 1,500 feet

of the properties included in the petition. An established Area of Regulated Groundwater Usage (ARGU) as defined by the Mecklenburg County Groundwater Well Regulations extends 1,500 feet around the contamination sites. In an ARGU where municipally supplied water is available water supply wells for potable water supply, irrigation or open loop geothermal systems may not be permitted or constructed on or within 1,000 feet of contamination sites. Wells may be permitted with special construction and sampling requirements between 1,000 and 1,500 feet of contamination sites.

Groundwater & Wastewater Services (GWS) records indicate that a water supply well has been registered and located within the bounds of parcel 187-011-02. Water supply wells should be protected during site development by flagging and fencing or be permanently abandoned in accordance with the Mecklenburg County Groundwater Well Regulations prior to site development commencing.

Storm Water Services Comments: No Comments

Solid Waste Comments: No Comments

**Department Contacts:**

Petitioners seeking to address individual comments and issues may follow up with the following Mecklenburg County staff:

*Air Quality Comments:* Megan Green - (megan.green@mecklenburgcountync.gov)

*Ground Water Services:* Shawna Caldwell - (shawna.caldwell@mecklenburgcountync.gov)

*Storm Water Services:* Myrette Stephen - (myrette.stephen@mecklenburgcountync.gov)

*Solid Waste Comments:* Joe Hack - (joe.hack@mecklenburgcountync.gov)

Additionally, please CC Erin Stanforth, (erin.stanforth@mecklenburgcountync.gov) on all communications to individual departments.

**MCAQ Scope of Review:**

Mecklenburg County Air Quality (MCAQ) has reviewed the petitions with regard to air quality regulations for stationary sources and demolition and/or renovation of structures (e.g. National Emission Standards for Hazardous Air Pollutants for asbestos). Comments may also be made regarding incompatible land uses, sources of Toxic Air Pollutants, proximity to Risk Management Plan facilities, and proximity to known nuisance conditions or sensitive populations. MCAQ has conducted the review based on information submitted by the petitioner, review of aerial photographs (as available through the Mecklenburg County Polaris system), review of the "Air Pollution Facility Information Online" database available from the MCAQ website, and review of Mecklenburg County Health Department records. The review is cursory based on limited information provided within petition applications and site plans.