



PERMITTING 8-INCH SEWER LATERALS (MAIN LINE EXTENSIONS)

SEWER (LATERAL) PERMITTING PROCESS (8" AND LARGER SERVING MORE THAN ONE STRUCTURE)

- Applies to Donated Projects and New Service Projects
 - Review Fees will not apply for New Service Reviews
 - Review Fees will apply for Donated Projects
- Donated Projects to permit additional LF and include in total LF

Pre-Construction:

- For New Services: Developers Engineer submits New Service Site Plan for review (10 business day review cycle)
 - Includes 8" sewer main extension (lateral) from existing sewer to site in question
 - Includes private MH (installed by CLT Water to allow for testing)
 - Includes sewer permit
 - Includes CLT Water title block – similar to cover sheet title block
 - Includes all associated new services
- Upon approval of site plan:
 - Permit Plan
 - Assign sewer extension/new services, including approved permitted plan to Contractor
 - CLT Water contractor completes installation(s)
 - Test sewer main extension after installation while contractor is still on site
 - Air Test
 - Mandrel Test

Post Construction:

- Developers Engineer submits As-Builts of sewer main extension for review
- Perform Final Inspection upon As-Built approval and passing tests
- Prepare Final Acceptance Letters upon completion of final inspection punch lists
- Certification Letter provided by CLT Water