



- | NO. | DESCRIPTION: |
|-----|--|
| 1. | KUPFERLE #9700-Y HYDRANT AUTO FLUSHER - YELLOW (INCLUDES #15-26). |
| 2. | 2" GALVANIZED STEEL PIPE (SCH 80). |
| 3. | TOP SECTION WATER VALVE BOX. |
| 4. | 2" S.S. OR RED BRASS (SCH 40), OR 2" DUCTILE IRON (FUSION BONDED EPOXY COATED) THREADED COUPLING (FNPT). |
| 5. | 18" X 18" X 6" CONCRETE PAD. |
| 6. | 2" S.S. OR RED BRASS PIPE (SCH 40). |
| 7. | 2" 90° S.S. OR RED BRASS BEND (SCH 40). |
| 8. | 2" S.S. OR RED BRASS PIPE (SCH 40). |
| 9. | 6 MIL HDPE PLASTIC FILM (54"X54"). |
| 10. | 16" X 16" X 2" PATIO PAVERS CONCRETE (9 EACH). |
| 11. | PAD LOCK (PROVIDED BY CLTW). |
| 12. | KUPFERLE #X707 BRASS 2" FNPT X 2 1/2" MNST HOSE NOZZLE. |
| 13. | LOCKING NOZZLE COLLAR - KUPFERLE #9708-Y. |
| 14. | CAMPBELL BLU-KROME 1/4" PROOF COIL CHAIN 5 LF. |
| 15. | KUPFERLE ADAPTOR. |
| 16. | 2" THREADED NIPPLE. |
| 17. | 2" X 2" X 2" TEE FIP THREAD. |
| 18. | PLUG/TAP. |
| 19. | WATER SAMPLE VALVE. |
| 20. | BRASS SAMPLING BIBB. |
| 21. | 2" SOLENOID CONTROL VALVE; P-220 SERIES. |
| 22. | MANUAL FLOW CONTROL KNOB. |
| 23. | HUNTER DIGITAL PROGRAMMABLE CONTROLLER WITH 9 VOLT LITHIUM BATTERY. |
| 24. | 2" FIP OUTLET (MAY BE HARD PIPE FOR DISCHARGES). |
| 25. | REMOVABLE DIFFUSER PLATE WITH 4 BOLTS/NUTS. |
| 26. | 2 1/2" FIRE HYDRANT NOZZLE COUPLING. |

- NOTES:**
- A. AUTO FLUSHER IS INTENDED FOR WARM WEATHER USE. ASSEMBLY SHOULD BE REMOVED DURING COLD WEATHER MONTHS TO AVOID DAMAGE DUE TO FREEZING.
 - B. MANUAL FLUSHING REQUIRED TO MAINTAIN WATER QUALITY DURING COLD WEATHER MONTHS.
 - C. PADLOCK PROVIDED BY CLTW.