



SECTION A-A

- NO. DESCRIPTION:**
1. LOW PRESSURE SEWER MAIN.
  2. CORE HOLE AND INSTALL FLEXIBLE BOOT CONNECTOR.
  3. BASE SECTION.
  4. RISER.
  5. EXISTING OR FINISHED GRADE.
  6. CONE.
  7. CROWN OF LOW PRESSURE SEWER MAIN TO BE INSTALLED AT SAME ELEVATION AS THE CROWN OF THE GRAVITY SEWER LINE ENTERING THE MANHOLE.
  8. RECEIVING GRAVITY SEWER.
  9. #57 STONE BASE, SUITABLE BEARING CAPACITY AS APPROVED BY GEOTECHNICAL ENGINEER.
  10. RESHAPE INVERT.
  11. CORROSION PROTECTION REQUIRED - SEE GRAVITY SEWER MANHOLE SPECIFICATIONS.

- NOTES:**
- A. INSIDE AND OUTSIDE DROPS SHALL NOT BE ALLOWED AT LOW PRESSURE SEWER CONNECTIONS TO MANHOLE.
  - B. TRACER WIRE NOT SHOWN FOR CLARITY. FOR TRACER WIRE INSTALLATION, REFER TO APPROPRIATE STANDARD DETAIL.