



NO. DESCRIPTION:

1. 1.5" SERVICE PIPE - SCH 80 PVC.
2. PVC ENCAPSULATED MAGNET.
3. 1 1/2" TRUE UNION PVC BALL VALVE.
4. 45° SCH 80 PVC BEND.
5. BARREL LOCK WITH RED CAP AND LOCKOUT TAG (FURNISHED BY CHARLOTTE WATER) - LOCK BALL VALVE CLOSED.
6. 1 1/2" THREADED OUTLET P.V.C. TEE W/1 1/2"x3/4" THREADED REDUCING BUSHING (SCH 80 PVC).
7. 3/4" BALL VALVE HOSE BIB (BRASS).
8. 6" #57 STONE BASE.
9. 1 1/2" TRUE UNION PVC BALL CHECK VALVE.
10. SERVICE BOX.
11. NCDOT SOLID CONCRETE CAPBLOCK (4"x4"x8").
12. BUSHING TO REDUCE SERVICE SIZE AND CAP.
13. PROPERTY LINE, ROAD RIGHT-OF-WAY OR CHARLOTTE WATER EASEMENT LINE.

NOTES:

- A. BARREL LOCK AND LOCKOUT TAG TO BE INSTALLED AFTER PRESSURE TEST, AND WILL BE REMOVED AFTER CHARLOTTE WATER INSPECTION OF PRIVATE LOW PRESSURE PUMP STATION - (CERTIFICATE OF OCCUPANCY HOLD WILL ALSO BE REMOVED).
- B. SERVICE BOX SHALL NOT BE IN SIDEWALKS OR DRIVEWAYS.
- C. TOP OF BOX SHALL BE FLUSH WITH FINISHED GRADE OF LOT.