

- 2019-115 Access roads shall have a min. 20' unobstructed clear width no matter which option you use.
- 2019-156 No comments.
- 2019-178 1- Fire department access road shall be capable of supporting 80,000 lbs. 2- Turn radius 30' inside and 42' outside. 3- Fire hydrant shall be located within 750' to the most remote point of building as truck travel for all buildings.
- 2019-181 1- Fire department access road shall be capable of supporting 80,000 lbs. 2- Fire hydrant shall be located within 750' to the most remote point of building as truck travel for all buildings. 3- For buildings that is equipped with a sprinkler system. A fire department connection shall be located within 200' of a fire hydrant for a NFPA 13 sprinkler system and 750' for a NFPA 13R sprinkler system.
- 2019-183 No comments.
- 2019-185 Maintain fire access roads 20' and turn radius 30' inside and 42' outside throughout property.