

2019-177 1- Fire department access road shall have a min. 20' unobstructed clear width and shall be capable of supporting 80,000 lbs. 2- Turn radius 30' inside and 42' outside. 3- Fire hydrant shall be located within 750' to the most remote point of building as truck travel for all buildings.

2019-179 1- Fire department access road shall have a min. 20' unobstructed clear width and shall be capable of supporting 80,000 lbs. 2- Fire department access road that exceeds 150' shall provide an approved turnaround. The turnaround shown is not in compliance. 3- Turn radius 30' inside and 42' outside. 4- Fire hydrant shall be located within 750' to the most remote point of building as truck travel for all buildings.