

# Rezoning Transportation Analysis

Petition Number: 2020-110

General Location Identifier: Tax ID 20516504

**From: Lakisha Hull**

[lakisha.hull@charlottenc.gov](mailto:lakisha.hull@charlottenc.gov)

704-432-5492

Revision Log:	Date	Description
	07/6/2020	First Review

**General Review Information**

The site is located along Sweden Road (city maintained, local road) and near Denmark Road (city maintained, local road). The site is in a corridor and is within the Arrowood Transit Plan Study Area.

**Potential Roadway Projects Near the Site:**

Denmark Road Extension (Sweden Rd to Arrowood Rd) with a 2-lane divided (median or center turn lane) with bike facilities and sidewalks

Old Pineville Road/England Street (Arrowood Rd to E Hebron St) with a 2-lane divided (median or center turn lane) with bike facilities and sidewalks

---

*CDOT's review of this rezoning petition is intended to provide consistency with council adopted policies, plans, standards and guidelines including, but not limited to, the [Transportation Action Plan \(TAP\)](#), [Vision Zero](#), [Urban Street Design Guidelines \(USDG\)](#), [Center, Corridor and Wedges](#), [Charlotte BIKES](#), [Traffic Impact Study Guidelines](#) and [Charlotte WALKS](#). With a commitment to design complete streets, this review is to ensure that the City's transportation network supports current and future land uses and includes streets that provide safe and comfortable mobility for motorists, pedestrians, bicyclists, and transit users.*

---

*This document is primarily for communication to Planning Department staff as part of the overall City staff analysis of the rezoning petition and includes an overall summary of the case from a transportation perspective, information on trip generation, and resolved or outstanding site plan concerns. Additional advisory information about the driveway permit process is provided for information only.*

---

Based on our review of the petition, we offer the following information for your consideration.

**Transportation Summary**

The site is located at the intersection of two local roads. CDOT will work with the petitioner during permitting once a site plan is submitted to ensure all applicable ordinance and area plan's transportation improvements are met.

**Trip Generation**

Scenario	Land Use	Intensity	Trip Generation (vehicle trips/day)	Source
Existing Use	TOD-CC	Too many uses to determine		Tax Record
Entitlement with Current Zoning	TOD-CC	Too many uses to determine		General Guidance from Planning
Proposed Zoning	Warehouse (2.5 acre of I-2)	37,500 SF	105	General Guidance From Planning

# Rezoning Transportation Analysis

Petition Number:2020-110

General Location Identifier: Tax ID 20516504

## Outstanding Issues

~~Strikeout~~ = Not an outstanding issue

1. **Traffic Study** A Traffic Impact Study is not necessary for the complete review of this petition due to the site generation less than 2500 daily trips. If the during the permitting process the site generates more than 2500 daily trips, then a traffic study will be required.

~~Resolved~~ Sample format for comment that is resolved

## Advisory Information

The following are requirements of the developer that must be satisfied prior to driveway permit approval. We recommend that the petitioner reflect these on the rezoning plan as-appropriate.

1. The setback for this district is measured from the back of the existing or future curbline as determined by CDOT and Planning during the permitting process.
2. According to the City of Charlotte's Driveway Regulations, CDOT has the authority to regulate/approve all private street/driveway and public street connections to the right-of-way of a street under the regulatory jurisdiction of the City of Charlotte.
3. Adequate sight triangles must be reserved at the existing/proposed street entrance(s). Two 35' x 35' sight triangles (and two 10' x 70' sight triangles on North Carolina Department of Transportation on NCDOT maintained streets) are required for the entrance(s) to meet requirements. All proposed trees, berms, walls, fences, and/or identification signs must not interfere with sight distance at the entrance(s). Such items should be identified on the site plan.
4. The proposed driveway connection(s) to public streets will require a driveway permit(s) to be submitted to CDOT (and the North Carolina Department of Transportation on NCDOT maintained streets) for review and approval. The exact driveway location(s) and type/width of the driveway(s) will be determined by CDOT during the driveway permit process. The locations of the driveway(s) shown on the site plan are subject to change in order to align with driveway(s) on the opposite side of the street and comply with City Driveway Regulations and the City Tree Ordinance.
5. All proposed commercial driveway connections to a future public street will require a driveway permit to be submitted to CDOT for review and approval.
6. Any fence or wall constructed along or adjacent to any sidewalk or street right-of-way requires a certificate issued by CDOT.
7. A Right-of-Way Encroachment Agreement is required for the installation of any non-standard item(s) (irrigation systems, decorative concrete pavement, brick pavers, etc.) within a proposed/existing City maintained street right-of-way by a private individual, group, business, or homeowner's/business association. An encroachment agreement must be approved by CDOT prior to the construction/installation of the non-standard item(s). Contact CDOT for additional information concerning cost, submittal, and liability insurance coverage requirements.