



MECKLENBURG COUNTY
Land Use & Environmental Services Agency

MEMORANDUM

To: Charlotte-Mecklenburg Planning Commission
From: Dylan J. Kirk, Mecklenburg County LUESA
Date: Thursday, February 25, 2021
Subject: Initial Rezoning Petition Comments

Charlotte-Mecklenburg Planning Commission
600 East Fourth Street Charlotte, North Carolina 28202

Mecklenburg County has reviewed the City of Charlotte rezoning petition below to identify regulatory requirements of the petitioner; inform the petitioner, planning staff, and other affected parties of such regulatory requirements; and identify potential effects on, and impacts from, nearby properties.

<u>Petitioner Information:</u> Scott Glover 2626 Glenwood Ave, Ste 550 Raleigh, NC 27608 704-334-3303 paul@urbandesignpartners.com	<u>Parcel GIS ID(s):</u> 16507103, 16507104, 16507105, 16507106, 16507128, 16507130, 16511318, 16511319, 16511321
--	---

2021-025: NVR, inc.

Air Quality Comments: Development of this site may require submission of an asbestos Notification of Demolition and Renovation to MCAQ due to possible demolition or relocation of an existing structure. A letter of notification and the required forms have been mailed directly to the petitioner by MCAQ.

Ground Water Services Comments: Groundwater & Wastewater Services records indicate contamination site(s) exist on or within 1,500 feet of the properties included in the petition. An established Area of Regulated Groundwater Usage (ARGU) as defined by the Mecklenburg County Groundwater Well Regulations extends 1,500 feet around the contamination sites. In an ARGU where municipally supplied water is available water supply wells for potable water supply, irrigation or open loop geothermal systems may not be permitted or constructed on or within 1,000 feet of contamination sites. Wells may be permitted with special construction and sampling requirements between 1,000 and 1,500 feet of contamination sites.

Groundwater & Wastewater Services (GWS) records indicate that a water supply well had been registered and located within the bounds of parcel 165-071-03. Water supply wells should be protected during site development by flagging and fencing or be permanently abandoned in accordance with the Mecklenburg County Groundwater Well Regulations prior to site development commencing.

Groundwater & Wastewater Services records indicate a registered septic system exists on parcel 165-071-03. No regulations govern the abandonment of septic systems; however, GWS does recommend that septic tanks be pumped by a NC Licensed Septic Hauler to remove any residual contents and then crushed and backfilled. This recommendation is made because improperly abandoned septic tanks may not be able to support the weight of vehicular traffic, structural foundations or people posing a safety hazard.

Information from property records indicate that the building(s) on parcels 165-071-03, 165-071-06, 165-071-30 and 165-113-19 uses or previously utilized oil, wood or coal heat. Based on this these properties may contain an underground or above ground fuel oil storage tank(s). The tank and its contents should be removed, following applicable NCDEQ guidance, prior to any demolition or grading activity.

Information from property records indicate that the building or former building on parcels 165-071-03 and 165-113-18 contains asbestos shingle and/or siding. If demolition or renovation is planned, then disturbance of Asbestos-Containing Materials (ACM) will likely be subject to the National Emissions Standards for Hazardous Air Pollutants (NESHAP) requirements for asbestos identification and abatement prior to demolition or renovation. Thus, this may include an asbestos survey conducted by a certified asbestos inspector and, if present, possible ACM removal by a certified asbestos contractor prior to demolition.

Storm Water Services Comments: No comments.

Solid Waste Comments: No petition comments.

Department Contacts:

Petitioners seeking to address individual comments and issues may follow up with the following Mecklenburg County staff:

Air Quality Comments: PJ McKenzie - (paul.mckenzie@mecklenburgcountync.gov)

Ground Water Services: Shawna Caldwell - (shawna.caldwell@mecklenburgcountync.gov)

Storm Water Services: Myrette Stephen - (myrette.stephen@mecklenburgcountync.gov)

Solid Waste Comments: Joe Hack - (joe.hack@mecklenburgcountync.gov)

Additionally, please CC Dylan Kirk, (dylan.kirk@mecklenburgcountync.gov) on all communications to individual departments.

MCAQ Scope of Review:

Mecklenburg County Air Quality (MCAQ) has reviewed the petitions with regard to air quality regulations for stationary sources and demolition and/or renovation of structures (e.g. National Emission Standards for Hazardous Air Pollutants for asbestos). Comments may also be made regarding incompatible land uses, sources of Toxic Air Pollutants, proximity to Risk Management Plan facilities, and proximity to known nuisance conditions or sensitive populations. MCAQ has conducted the review based on information submitted by the petitioner, review of aerial photographs (as available through the Mecklenburg County Polaris system), review of the "Air Pollution Facility Information Online" database available from the MCAQ website, and review of Mecklenburg County Health Department records. The review is cursory based on limited information provided within petition applications and site plans.