



MECKLENBURG COUNTY
Land Use & Environmental Services Agency

MEMORANDUM

To: Charlotte-Mecklenburg Planning Commission
From: LUESA, Mecklenburg County
Date: 5.27.21
Subject: Rezoning Petition Comments

Charlotte-Mecklenburg Planning Commission
600 East Fourth Street Charlotte, North Carolina 28202

Mecklenburg County has reviewed the City of Charlotte rezoning petition below to identify regulatory requirements of the petitioner; inform the petitioner, planning staff, and other affected parties of such regulatory requirements; and identify potential effects on, and impacts from, nearby properties.

<u>Petitioner Information:</u> SRL Central Avenue Properties LLC 2629 Central Avenue Charlotte, NC 28205 704-234-7488 rwf@russellwfergusson.com	<u>Parcel GIS ID(s):</u> 09509222
---	---

2021-060: 2506 Central Ave

Air Quality Comments: Development of this site may require submission of an asbestos Notification of Demolition and Renovation to MCAQ due to possible demolition or relocation of an existing structure. A letter of notification and the required forms have been mailed directly to the petitioner by MCAQ.

Ground Water Services Comments: Groundwater & Wastewater Services records indicate contamination site(s) exist on or within 1,500 feet of the property included in the petition. An established Area of Regulated Groundwater Usage (ARGU) as defined by the Mecklenburg County Groundwater Well Regulations extends 1,500 feet around the contamination sites. In an ARGU where municipally supplied water is available water supply wells for potable water supply, irrigation or open loop geothermal systems may not be permitted or constructed on or within 1,000 feet of contamination sites. Wells may be permitted with special construction and sampling requirements between 1,000 and 1,500 feet of contamination sites.

Information from property records does not indicate the current use of oil heat, but since records indicate structures were built in 1953, the property may contain an underground or above ground fuel oil storage tank. Any existing tank and its contents should be removed, following applicable NCDEQ guidance, prior to any demolition or grading activity.

A Subsurface Investigation Permit (SIP) was issued for this parcel.

If any MWs are identified within the project boundary GWS recommends that the petitioner either protect the wells from damage by flagging and fencing during site development or permanently abandon the wells per the Mecklenburg County Groundwater Well Regulations prior to any demolition or grading activity occurring and conduct survey to locate the monitoring wells. A current SIP from GWS is required for permanent well abandonments. The abandonments must be completed by a North Carolina Certified Well Contractor.

NCDEQ UST Incidents 19356 and 40716 are documented on this parcel, Texaco Food Mart.

Please contact Dan Bowser for more information.

Daniel P. Bowser, PG
Hydrogeologist
North Carolina Department of Environmental Quality
Underground Storage Tank Section - Corrective Action Branch
(704) 235-2172
dan.bowser@ncdenr.gov
610 East Center Ave
Suite 301
Mooresville, North Carolina 28115

Storm Water Services Comments: No comments

Solid Waste Comments: No comments

Department Contacts:

Petitioners seeking to address individual comments and issues may follow up with the following Mecklenburg County staff:

Air Quality Comments: PJ McKenzie - (paul.mckenzie@mecklenburgcountync.gov)

Ground Water Services: Shawna Caldwell - (shawna.caldwell@mecklenburgcountync.gov)

Storm Water Services: Myrette Stephen - (myrette.stephen@mecklenburgcountync.gov)

Solid Waste Comments: Joe Hack - (joe.hack@mecklenburgcountync.gov)

PEOPLE ● PRIDE ● PROGRESS ● PARTNERSHIP
2145 Suttle Avenue ● Charlotte, North Carolina 28208 ● Fax 980.335.2253
www.mecknc.gov

Additionally, please CC Dylan Kirk, (dylan.kirk@mecklenburgcountync.gov) on all communications to individual departments.

MCAQ Scope of Review:

Mecklenburg County Air Quality (MCAQ) has reviewed the petitions with regard to air quality regulations for stationary sources and demolition and/or renovation of structures (e.g. National Emission Standards for Hazardous Air Pollutants for asbestos). Comments may also be made regarding incompatible land uses, sources of Toxic Air Pollutants, proximity to Risk Management Plan facilities, and proximity to known nuisance conditions or sensitive populations. MCAQ has conducted the review based on information submitted by the petitioner, review of aerial photographs (as available through the Mecklenburg County Polaris system), review of the “Air Pollution Facility Information Online” database available from the MCAQ website, and review of Mecklenburg County Health Department records. The review is cursory based on limited information provided within petition applications and site plans.