



**MECKLENBURG COUNTY**  
**Land Use & Environmental Services Agency**

**MEMORANDUM**

To: Charlotte-Mecklenburg Planning Commission

From: LUESA, Mecklenburg County

Date: 4.28.22

Subject: Rezoning Petition Comments

Charlotte-Mecklenburg Planning Commission  
600 East Fourth Street Charlotte, North Carolina 28202

Mecklenburg County has reviewed the City of Charlotte rezoning petition below to identify regulatory requirements of the petitioner; inform the petitioner, planning staff, and other affected parties of such regulatory requirements; and identify potential effects on, and impacts from, nearby properties.

<b><u>Petitioner Information:</u></b> Lennar Carolinas, LLC 6701 Carmel Road Charlotte, NC, 28226 Home Phone: 704-200-2637 brittany.lins@alexanderricks.com	<b><u>Parcel GIS ID(s):</u></b> 11306113
---	---

**2021-257: Amos Smith Residential**

*Air Quality Comments:* No comment on this rezoning petition.

*Ground Water Services Comments:* Groundwater & Wastewater Services records indicate contamination site(s) exist on or within 1,500 feet of the property included in the petition. An established Area of Regulated Groundwater Usage (ARGU) as defined by the Mecklenburg County Groundwater Well Regulations extends 1,500 feet around the contamination sites. In an ARGU where municipally supplied water is available water supply wells for potable water supply, irrigation or open loop geothermal systems may not be permitted or constructed on or within 1,000 feet of contamination sites. Wells may be permitted with special construction and sampling requirements between 1,000 and 1,500 feet of contamination sites.

*Storm Water Services Comments:*

- The project is within the Lower Lake Wylie Critical Watershed Area which has a maximum cap of 50% Built Upon Area (BUA) and requires storm water treatment. The project must also comply with the City of Charlotte Post Construction Ordinance.
- Due to the proximity to Paw Creek Cove, it is requested that the developer commit to the installation and implementation of a continuous stream monitoring station downstream of the project to monitor turbidity in the stream 24 hours/day during construction and provide alerts to erosion control inspectors if exceedances occur. Coordinate with Storm Water Services – Water Quality.
- It is requested that the project initiate aggressive, enhanced erosion control such as enlarged basins, enhanced silt fencing, and staged, limited grading as specified by Charlotte Land Development.

*Solid Waste Comments:* No comments

**Department Contacts:**

Petitioners seeking to address individual comments and issues may follow up with the following Mecklenburg County staff:

*Air Quality Comments:* PJ McKenzie - (paul.mckenzie@mecklenburgcountync.gov)

*Ground Water Services:* Shawna Caldwell - (shawna.caldwell@mecklenburgcountync.gov)

*Storm Water Services:* Myrette Stephen - (myrette.stephen@mecklenburgcountync.gov)

*Solid Waste Comments:* Joe Hack - (joe.hack@mecklenburgcountync.gov)

Additionally, please CC Erin Stanforth, (erin.stanforth@mecklenburgcountync.gov) on all communications to individual departments.

**MCAQ Scope of Review:**

Mecklenburg County Air Quality (MCAQ) has reviewed the petitions with regard to air quality regulations for stationary sources and demolition and/or renovation of structures (e.g. National Emission Standards for Hazardous Air Pollutants for asbestos). Comments may also be made regarding incompatible land uses, sources of Toxic Air Pollutants, proximity to Risk Management Plan facilities, and proximity to known nuisance conditions or sensitive populations. MCAQ has conducted the review based on information submitted by the petitioner, review of aerial photographs (as available through the Mecklenburg County Polaris system), review of the “Air Pollution Facility Information Online” database available from the MCAQ website, and review of Mecklenburg County Health Department records. The review is cursory based on limited information provided within petition applications and site plans.